KETCHIKAN PUBLIC UTILITIES

# KPU

Your Community, Your Utility

2021-2025 CAPITAL IMPROVEMENT PROGRAM

# CITY OF KETCHIKAN, ALASKA 2021 - 2025 KETCHIKAN PUBLIC UTILITIES CAPITAL IMPROVEMENT PROGRAM

# **CONTENTS**

2021 Capital Budget	A-1
Summary of Projects by Division - All Years	A-4
Summary of Projects by Funding Source - All Years	A-7
General Manager	B-1
Electric	C-1
Telecommunications	D-1
Water	F-1

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program 2021 Capital Budget

	Revenues/			Revenue	2020
Department/Division/Project	Reserves	Grants	Other	Bonds	Total
Administration					
Financial & Accounting Information System	20,000				20,000
Administration Division Total	20,000				20,000
Sales, Marketing & Customer Service					
None					
Sales, Marketing & Customer Service Division Total					
Electric Division					
Beaver Falls Project Relicensing	120,000				120,000
Bailey Unit No. 3 Rehabilitation	400,000				400,000
Bailey Unit No. 1 Rehabilitation	850,000				850,000
Diesel Generation Modernization	60,000				60,000
Beaver Falls Switch Gear Replacement	1,535,000				1,535,000
Whitman Tailrace Modification	25,000				25,000
Bailey Generator Radiator Replacement	25,000				25,000
Ketchikan International Airport & Pennock Is. Upgrade	50,000				50,000
Silvis Substation Upgrade	125,000				125,000
AMI, Meters and Meter Replacement Parts	65,000				65,000
Transformer Purchase	85,000				85,000
Battery System and Chargers	19,000				19,000
Reimbursable Projects	25,000				25,000
Warehouse Roof Repair and Replacement	220,000				220,000
Operating Equipment	263,000				263,000
Additional Projects	164,000				164,000
Electric Division Total	4,031,000				4,031,000

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program 2021 Capital Budget

	Revenues/			Revenue	2020
Department/Division/Project	Reserves	Grants	Other	Bonds	Total
Telecommunications Division					
Normal Growth and Repair - Buildings	10,000				10,000
Normal Growth and Repair - Copper Cable	10,000				10,000
Normal Growth and Repair - Fiber Cable	100,000				100,000
Normal Growth and Repair - CO Transmission	150,000				150,000
Normal Growth and Repair - Expansion	5,000				5,000
Normal Growth and Repair - Provisioning	10,000				10,000
Fiber to the Home	50,000				50,000
Remote Cabinets for Advanced Services	10,000				10,000
Core Network Upgrade	100,000				100,000
Server Environment	50,000				50,000
Multi-Dwelling Unit Project	100,000				100,000
Operating Equipment	15,000				15,000
PC Hardware & Software	40,000				40,000
Power Expansion/Reclamation	5,000				5,000
Network Monitoring	100,000				100,000
Headend Expansion	10,000				10,000
Video Set Top Boxes	25,000				25,000
4G LTE	60,000				60,000
Hosted	100,000				100,000
Wi-Fi	50,000				50,000
Internet Expansion				1,175,000	1,175,000
Telecommunications Division Total	1,000,000			1,175,000	2,175,000

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program 2021 Capital Budget

	Revenues/			Revenue	2020
Department/Division/Project	Reserves	Grants	Other	Bonds	Total
Water Division					
Filtration Facility-Preliminary Preparation Tasks	386,700				386,700
Schoenbar Water Mains - (Charter School - Middle School)				7,092,499	7,092,499
Water Meters - Business & Commercial Customers				756,178	756,178
Federal Act - Risk & Resilience Assessment	150,000				150,000
SCADA PLC Controllers	260,000				260,000
Water Distribution Grid Improvements	30,000				30,000
Additional Projects	40,000				40,000
Water Service Upgrade Program	15,000				15,000
Backflow Prevention Program	15,000				15,000
Water Division Total	896,700			7,848,677	8,745,377
GRAND TOTAL	5,947,700			9,023,677	14,971,377

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program Summary of Projects by Division - All Years

	Prior						Five Year	Project
Division/Project	Years	2021	2022	2023	2024	2025	Total	Total
Administration	400.000	00.000					00.000	450.000
Financial & Accounting Information System Implementation	438,992	20,000					20,000	458,992
Administration Total	438,992	20,000					20,000	458,992
Electric Division								
Beaver Falls Project Relicensing	443,000	120,000	37,000				157,000	600,000
Bailey Unit No. 3 Rehabilitation	500,000	400,000					400,000	900,000
Bailey Unit No. 1 Rehabilitation	15,835	850,000					850,000	865,835
Diesel Generation Modernization	120,000	60,000					60,000	180,000
Beaver Falls Switch Gear Replacement	105,000	1,535,000					1,535,000	1,640,000
Generator Rewind & Repair			650,000	700,000			1,350,000	1,350,000
Whitman Tailrace Modification	11,291	25,000					25,000	36,291
Ketchikan Tunnel Penstock Valves Replacement	50,000		50,000	200,000			250,000	300,000
Bailey Exhaust Stack Re-Coating			25,000	225,000			250,000	250,000
Bailey Generator Radiator Replacement		25,000	300,000				325,000	325,000
Beaver Falls Governor Upgrade				250,000			250,000	250,000
Bailey Generator No. 4 Wartsilia PLC Upgrade			115,000				115,000	115,000
Generation Equipment Planning, Cleaning & Testing	191,395		50,000	50,000			100,000	291,395
Ketchikan Lakes Underground			250,000				250,000	250,000
Ketchikan International Airport & Pennock Is. Upgrade	245,000	50,000	140,000	250,000	25,000		465,000	710,000
Downtown Underground Upgrade	310,459		25,000	25,000	25,000		75,000	385,459
Silvis Substation Upgrade		125,000					125,000	125,000
AMI, Meters and Meter Replacement Parts		65,000	185,000	125,000	125,000	125,000	625,000	625,000
Transformer Purchase		85,000	90,000	95,000	100,000	105,000	475,000	475,000
Battery Systems and Chargers	17,000	19,000	56,000	76,000	46,000	50,500	247,500	264,500
Reimbursable Projects		25,000	150,000	125,000	125,000	125,000	550,000	550,000
34.5 kV Tie Breaker and Relay Spares				50,000		105,000	155,000	155,000
Warehouse Roof Repair & Replacement	50,000	220,000					220,000	270,000
Bailey Fuel Tank Painting			100,000				100,000	100,000
Bailey Mooring Dolphin Replacement			110,000				110,000	110,000
Operating Equipment		263,000	375,500	275,000	275,000	275,000	1,463,500	1,463,500
Vehicles & Moving Equipment			165,000	475,000	380,000	190,000	1,210,000	1,210,000
Additional Projects		164,000	164,000	164,000	164,000	164,000	820,000	820,000
Beaver Falls Powerhouse Exterior	36,070		600,000		·		600,000	636,070
Vehicle Lift Replacement			80,000				80,000	80,000
Electric Division Total	2,095,050	4,031,000	3,717,500	3,085,000	1,265,000	1,139,500	13,238,000	15,333,050

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program Summary of Projects by Division - All Years

	Prior						Five Year	Project
Division/Project	Years	2021	2022	2023	2024	2025	Total	Total
Telecommunications Division								
Normal Growth and Repair - Buildings		10,000	25,000	25,000	30,000	35,000	125,000	125,000
Normal Growth and Repair - CO Switching			500,000	150,000	100,000	50,000	800,000	800,000
Normal Growth and Repair - Copper Cable		10,000	20,000	20,000	20,000	25,000	95,000	95,000
Normal Growth and Repair - Fiber Cable		100,000	200,000	150,000	150,000	150,000	750,000	750,000
Normal Growth and Repair - CO Transmission		150,000	150,000	150,000	150,000	150,000	750,000	750,000
Normal Growth and Repair - Expansion		5,000	25,000	25,000	25,000	30,000	110,000	110,000
Normal Growth and Repair - Provisioning		10,000	50,000	150,000	100,000	50,000	360,000	360,000
Fiber to the Home		50,000	75,000	75,000	75,000	75,000	350,000	350,000
Remote Cabinets for Advanced Services		10,000	25,000	25,000	25,000	35,000	120,000	120,000
Core Network Upgrade		100,000	100,000	800,000	700,000	500,000	2,200,000	2,200,000
Server Environment		50,000	100,000	150,000	200,000	150,000	650,000	650,000
Multi-Dwelling Unit Project		100,000	200,000	200,000	200,000	200,000	900,000	900,000
Operating Equipment		15,000	50,000	60,000	60,000	65,000	250,000	250,000
PC Hardware & Software		40,000	45,000	50,000	50,000	55,000	240,000	240,000
Power Expansion/Reclamation		5,000	25,000	25,000	30,000	35,000	120,000	120,000
Visual Mapping Software			25,000	25,000	25,000	30,000	105,000	105,000
Network Monitoring		100,000	100,000	100,000	120,000	130,000	550,000	550,000
Vehicle Acquisition			100,000	100,000	150,000	150,000	500,000	500,000
Security				100,000	120,000	200,000	420,000	420,000
Headend Expansion		10,000	40,000	35,000	35,000	25,000	145,000	145,000
IPv4 Addressing			100,000	50,000	50,000		200,000	200,000
Video Set Top Boxes		25,000	50,000	25,000	25,000	10,000	135,000	135,000
4G/LTE		60,000	150,000	150,000	150,000	150,000	660,000	660,000
Microwave			25,000	25,000	25,000	25,000	100,000	100,000
Hosted		100,000	150,000	200,000	250,000	200,000	900,000	900,000
Wi-Fi		50,000	50,000	75,000	75,000	100,000	350,000	350,000
Internet Expansion	10,425,000	1,175,000					1,175,000	11,600,000
Telecommunications Division Total	10,425,000	2,175,000	2,380,000	2,940,000	2,940,000	2,625,000	13,060,000	23,485,000
		·	·				·	

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program Summary of Projects by Division - All Years

	Prior						Five Year	Project
Division/Project	Years	2021	2022	2023	2024	2025	Total	Total
Water Division								
Water Filtration Facility Project	138,300	386,700					386,700	525,000
Schoenbar Water Mains - (Charter School - Middle School)	427,000	7,092,499					7,092,499	7,519,499
Water Meters - Business & Commercial Customers	512,840	756,178					756,178	1,269,018
Federal Act - Risk & Resilience Assessment		150,000					150,000	150,000
SCADA PLC Controllers	50,000	260,000		265,000		285,000	810,000	860,000
Water Distribution Grid Improvements		30,000	30,000	30,000	30,000	30,000	150,000	150,000
Additional Projects		40,000	40,000	40,000	40,000	40,000	200,000	200,000
Water Service Upgrade Program		15,000	15,000	15,000	15,000	15,000	75,000	75,000
Backflow Prevention Program		15,000	15,000	15,000	15,000	15,000	75,000	75,000
Highlands Reservoir Property Acquisition					270,000		270,000	270,000
Second Avenue Utility Improvements			15,000			1,300,800	1,315,800	1,315,800
West Fairy Chasm Utility Improvements			15,000			550,600	565,600	565,600
Skyline Water Main Replacement			10,000			360,800	370,800	370,800
Denali Ave. Utility Improvements			15,000			512,000	527,000	527,000
Evergreen Ave. Utility Improvements			15,000			440,000	455,000	455,000
Utility Vehicles			37,500	118,000	94,000		249,500	249,500
Water Division Total	1,128,140	8,745,377	207,500	483,000	464,000	3,549,200	13,449,077	14,577,217
TOTAL	14,087,182	14,971,377	6,305,000	6,508,000	4,669,000	7,313,700	39,767,077	53,854,259

# Ketchikan Public Utilities

# 2021 - 2025 Capital Improvement Program Summary of Projects by Funding Source - All Years

Division/Project	Prior Years	Revenue Generating Fund	Grants	Other	Revenue Bonds	State Drinking Water Loan Fund	Total
Administration	100.10		0.0	1	1		
Financial & Accounting Information System Implementation	438,992	20,000					458,992
Administration Total	438,992	20,000					458,992
Electric Division							
Beaver Falls Project Relicensing	443,000	157,000					600,000
Bailey Unit No. 3 Rehabilitation	500,000	400,000					900,000
Bailey Unit No. 1 Rehabilitation	15,835	850,000					865,835
Diesel Generation Modernization	120,000	60,000					180,000
Beaver Falls Switch Gear Replacement	105,000	1,535,000					1,640,000
Generator Rewind & Repair	,	1,350,000					1,350,000
Whitman Tailrace Modification	11,291	25,000					36,291
Ketchikan Tunnel Penstock Valves Replacement	50,000	250,000					300,000
Bailey Exhaust Stack Re-Coating	·	250,000					250,000
Bailey Generator Radiator Replacement		325,000					325,000
Beaver Falls Governor Upgrade		250,000					250,000
Bailey Generator No. 4 Wartsila PLC Upgrade		115,000					115,000
Generation Equipment Planning, Cleaning & Testing	191,395	100,000					291,395
Ketchikan Lakes Underground		250,000					250,000
Ketchikan International Airport & Pennock Is. Upgrade	245,000	465,000					710,000
Downtown Underground Upgrade	310,459	75,000					385,459
Silvis Substation Upgrade		125,000					125,000
AMI, Meters and Meter Replacement Parts		625,000					625,000
Transformer Purchase		475,000					475,000
Battery Systems & Chargers	17,000	247,500					264,500
Reimbursable Projects		550,000					550,000
34.5 kV Tie Breaker and Relay Spares		155,000					155,000
Warehouse Roof Repair and Replacement	50,000	220,000					270,000
Bailey Fuel Tank Painting		100,000					100,000
Bailey Mooring Dolphin Replacement		110,000					110,000
Operating Equipment		1,463,500					1,463,500
Vehicles & Moving Equipment		1,210,000					1,210,000
Additional Projects		820,000					820,000
Beaver Falls Powerhouse Exterior	36,070	600,000					636,070
Vehicle Lift Replacement		80,000					80,000
Electric Division Total	2,095,050	13,238,000					15,333,050

# Ketchikan Public Utilities

# 2021 - 2025 Capital Improvement Program Summary of Projects by Funding Source - All Years

Division/Project	Prior Years	Revenue Generating Fund	Grants	Other	Revenue Bonds	State Drinking Water Loan Fund	Total
Telecommunications Division	1						
Normal Growth and Repair - Buildings		125,000					125,000
Normal Growth and Repair - CO Switching		800,000					800,000
Normal Growth and Repair - Copper Cable		95,000					95,000
Normal Growth and Repair - Fiber Cable		750,000					750,000
Normal Growth and Repair - CO Transmission		750,000					750,000
Normal Growth and Repair - Expansion		110,000					110,000
Normal Growth and Repair - Provisioning		360,000					360,000
Fiber to the Home		350,000					350,000
Remote Cabinets for Advanced Services		120,000					120,000
Core Network Upgrade		2,200,000					2,200,000
Server Environment		650,000					650,000
Multi-Dwelling Unit Project		900,000					900,000
Operating Equipment		250,000					250,000
PC Hardware & Software		240,000					240,000
Power Expansion/Reclamation		120,000					120,000
Visual Mapping Software		105,000					105,000
Network Monitoring		550,000					550,000
Vehicle Acquisition		500,000					500,000
Security		420,000					420,000
Headend Expansion		145,000					145,000
IPv4 Addressing		200,000					200,000
Video Set Top Boxes		135,000					135,000
4G/LTE		660,000					660,000
Microwave		100,000					100,000
Hosted		900,000					900,000
Wi-FI		350,000					350,000
Internet Expansion	10,425,000	1,175,000					11,600,000
Telecommunications Division Total	10,425,000	13,060,000					23,485,000

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program Summary of Projects by Funding Source - All Years

Division/Project	Prior Years	Revenue Generating Fund	Grants	Other	Revenue Bonds	State Drinking Water Loan Fund	Total
Water Division							
Water Filtration Facility Project	138,300	386,700					525,000
Schoenbar Water Mains - (Charter School - Middle School)	427,000	·				7,092,499	7,519,499
Water Meters - Business & Commercial Customers	512,840					756,178	1,269,018
Federal Act - Risk & Resilience Assessment		150,000					150,000
SCADA PLC Controllers	50,000	810,000					860,000
Water Distribution Grid Improvements		150,000					150,000
Additional Projects		200,000					200,000
Water Service Upgrade Program		75,000					75,000
Backflow Prevention Program		75,000					75,000
Highlands Reservoir Property Acquisition			135,000			135,000	270,000
Second Avenue Utility Improvements		15,000	650,400			650,400	1,315,800
West Fairy Chasm Utility Improvements		15,000	275,300			275,300	565,600
Skyline Water Main Replacement		10,000	180,400			180,400	370,800
Denali Ave. Utility Improvements		15,000	256,000			256,000	527,000
Evergreen Ave. Utility Improvements		15,000	220,000			220,000	455,000
Utility Vehicles		249,500					249,500
Water Division Total	1,128,140	2,166,200	1,717,100			9,565,777	14,577,217
TOTAL	14,087,182	28,484,200	1,717,100		1	9,565,777	53,854,259

# Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program

**Department: General Manager** 

			Α	dopted 202	1	ı	Projected R	equirement	s	
Project Title	Priority	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Financial & Accounting Information System Implementation	1	438,992	18,400	1,600	20,000					458,992
Total		438,992	18,400	1,600	20,000					458,992

			A	dopted 202	1	Projected Requirements				
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund		438,992	18,400	1,600	20,000					458,992
Total		438,992	18,400	1,600	20,000					458,992

Department: KPU General Manager **Project Priority:** Project Number: Project Title: Financial & Accounting Information System Start Date: 01/07 Estimated Project Cost: Implementation End Date: Design 12/21 Land/Right-of-Way Description: Consultation 51,975 The City awarded a contract to New World Systems for the acquisition of new financial and accounting information system and Construction began implementation in September 2011. Anticipated project completion is December 2021. The total project cost is estimated Equip, Software & Implementation Services 391,517 at \$918,000. Finance is requesting that remaining funds that have been appropriated for this project be carried over to 2021. Other - Training 15,500 Funds will be used for hardware and software contingencies and New World resources to supplement the Finance Department's 458,992 Project Total

efforts during critical phases of the continuing implementation process. Scheduled for completion in 2021 is financial reporting, electronic personnel action forms and e-suites. The cost of this project is being funded equally by General Government and KPU.

				Adopted 2021			Projected R	equirements		
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund		438,992	18,400	1,600	20,000					458,992
Total		438,992	18,400	1,600	20,000					458,992

## Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program Division: Electric

Generation (Hydro and Dissel) Projects   Beaver Falls Project Relicenshing   1					Adopted 2021	1	Projected Requirements				
Comparation (Hydro and Diseal) Projects   Beaver Falls Project Relicensing   1			Prior	Reappro-	New						Total
Beaver Falls Project Relicensing   1	Project Title	Priority	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Baswer Falls December   1	Generation (Hydro and Diesel) Projects										
Balley Unit No. 1 Rehabilitation		1	443 000	80 000	40 000	120 000	37 000				600.0
Balley Unit No. 1 Rehabilitation	, .	1	-,	,	.0,000	-,	01,000				900,0
Diesel Ceneration Modernization   5   120,000   60,000   1,505,000   60,000   1,505,000					15 835	,					865,8
Beaver Falls Switch Gear Replacement 6 105,000 35,000 1,500,000 1,535,000 650,000 700,					10,000	,					180,0
Semeration Rewind & Repair   7					1 500 000	,					1,640,0
Whitman Tailrace Modification   8	·		100,000	00,000	1,000,000	1,000,000	650 000	700 000			1,350,
Matchikan Tunnel Penstock Valves Replacement   10   50,000   25,000   200,000   225,	•	1	11 201		25,000	25,000	030,000	700,000			36,2
Balley Exhaust Stack Re-Coaling					23,000	25,000	50,000	200 000			300,
Bailey Generator Radiator Replacement 25 Beaver Falls Governor Upgrade 27 Bailey Generator No. 4 Wartslia PLC Upgrade 28 Generation Equipment Planning, Cleaning & Testing 30 191,395 50,000 50	·		30,000				,	,			250.0
Beaver Falls Governor Upgrade   27   30   115,000   250,000   30	,				25,000	25,000		223,000			325,0
Bailey Generatior No. 4 Wartsila PLC Upgrade Generation Equipment Planning, Cleaning & Testing 30 191,395  Transmission and Distribution Projects Ketchikan Lakes Underground 9 Ketchikan International Airport & Pennock Upgrade 11 245,000 Downtown Underground Upgrade 12 310,459 Silvis Substation Upgrade 13 14 125,000 AMI, Meters, Meter Replacement Parts 14 15,000 Battery System and Chargers 16 17,000 Battery System and Chargers 16 17,000 Battery System and Chargers 16 17,000 Battery Bystem and Chargers 16 17,000 Battery Bystem and Chargers 17 Bailey Morning Dolphin Replacement 18 Operating Equipment 19 263,000 Bailey Morning Dolphin Replacement 19 283,000 Bailey Morning Dolphin Replacement 19 283,000 Beaver Fails Powerhouse Exterior 26 36,070 Vehicles & Moving Equipment 29  Total  10 2,095,050 1,654,165 2,376,835 4,031,000 3,717,500 3,085,000 1,265,000 1,265,000 1,139,500 1,1	,				23,000	23,000	300,000	250,000			250,
Seminaria	, ,						115 000	250,000			115,0
Transmission and Distribution Projects   Ketchikan Lakes Underground   9   Ketchikan International Airport & Pennock Upgrade   11   245,000   50,000   50,000   140,000   250,000   25,000   2		_	101 205				-,	E0 000			291,3
Retchikan Lakes Underground	Generation Equipment Planning, Cleaning & Testing	30	191,395				50,000	50,000			291,3
Ketchikan International Airport & Pennock Upgrade   11	Transmission and Distribution Projects										
Downtown Underground Upgrade   12   310,459   125,000   25,000		9					250,000				250,0
Downtown Underground Upgrade   12   310,459   125,000   25,000	Ketchikan International Airport & Pennock Upgrade	11	245,000		50,000	50,000	140,000	250,000	25,000		710,0
AMI, Meters, Meter Replacement Parts 14		12	310,459				25,000	25,000	25,000		385,4
Transformer Purchase	Silvis Substation Upgrade	13		125,000		125,000					125,0
Transformer Purchase	AMI, Meters, Meter Replacement Parts	14		-	65,000	65,000	185,000	125,000	125,000	125,000	625,0
Reimbursable Projects 23 24 25,000 25,000 155,000 125,000 125,000 125,000 125,000 125,000 105,	Transformer Purchase	15			85,000	85,000	90,000	95,000	100,000	105,000	475,0
Reimbursable Projects 23 24 25,000 25,000 150,000 125,000 125,000 125,000 105,000 105,000 24,5 kV Breaker and Relay Spares 24 25 50,000 120,000 100,000 220,000 50,000 125,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 105,000 100,000	Battery System and Chargers	16	17,000		19,000	19,000	56,000	76,000	46,000	50,500	264,5
34.5 kV Breaker and Relay Spares 24		23			25.000	25.000	150,000	125.000	125.000	125.000	550,0
Warehouse Roof Repair and Replacement         2         50,000         120,000         100,000         220,000         100,000         275,000		24			ŕ	,	·		,		155,0
Warehouse Roof Repair and Replacement         2         50,000         120,000         100,000         220,000         100,000         275,000	General Plant Projects										
Bailey Fuel Tank Painting		2	50,000	120 000	100 000	220 000					270,0
Bailey Mooring Dolphin Replacement   18	· · · · · · · · · · · · · · · · · · ·		00,000	120,000	.00,000	220,000	100 000				100,0
Operating Equipment         19         263,000         263,000         375,500         275,000	,						,				110,0
Vehicles & Moving Equipment         20 21 21 21 22         164,000 16					263 000	263 000		275 000	275 000	275 000	1,463,
Additional Projects Beaver Falls Powerhouse Exterior Vehicle Lift Replacement  Total  2,095,050  Revenue Generating Fund  21 2,095,050  21 36,070 29  36,070 20 20 20 20 20 20 20 20 20 20 20 20 20		_			200,000	200,000		,	-,	-,	1,210,
Beaver Falls Powerhouse Exterior   26   36,070     600,000   80,000	•	_			164 000	164 000		,	,		820.
Vehicle Lift Replacement         29         80,000         80,000         1,265,000         1,139,500         1           Total         2,095,050         1,654,165         2,376,835         4,031,000         3,717,500         3,085,000         1,265,000         1,139,500         1           Source of Funds         Reappropriated Funding Fund         New Funding Fund         Total Funding Fund         2022         2023         2024         2025         1           Revenue Generating Fund         2,095,050         1,654,165         2,376,835         4,031,000         3,717,500         3,085,000         1,265,000         1,139,500         1	•		36.070		104,000	104,000	. ,	104,000	104,000	104,000	636,
Total 2,095,050 1,654,165 2,376,835 4,031,000 3,717,500 3,085,000 1,265,000 1,139,500 1    Adopted 2021   Projected Requirements		_	30,070								80,
New   Projected Requirements   Prior   Reappro-   New   Projected Funds   Projected Requirements   Prior   Projected Requirements   Prior   Reappro-   New   Projected Requirements   Prior   Projected Requirements   Prior   New   Projected Requirements   Prior   New   Projected Requirements   Prior   New   Projected Requirements   Projected Re	venicie Liit Nepiacement	29					80,000				60,
Source of Funds         Prior Years         Reappropriated Prior Priated         New Funding         Total         2022         2023         2024         2025         1           Revenue Generating Fund         2,095,050         1,654,165         2,376,835         4,031,000         3,717,500         3,085,000         1,265,000         1,139,500         1	Total		2,095,050	1,654,165	2,376,835	4,031,000	3,717,500	3,085,000	1,265,000	1,139,500	15,333,
Source of Funds         Prior Years         Reappropriated Funding         New Funding         Total         2022         2023         2024         2025         1           Revenue Generating Fund         2,095,050         1,654,165         2,376,835         4,031,000         3,717,500         3,085,000         1,265,000         1,139,500         1					Adonted 2021	1		Projected R	equirements		
Source of Funds         Years         priated         Funding         Total         2022         2023         2024         2025           Revenue Generating Fund         2,095,050         1,654,165         2,376,835         4,031,000         3,717,500         3,085,000         1,265,000         1,139,500         1			Prior			-		ojootoa it			Total
Revenue Generating Fund 2,095,050 1,654,165 2,376,835 4,031,000 3,717,500 3,085,000 1,265,000 1,139,500 1	Source of Funds		_		-	Total	2022	2023	2024	2025	Projec
											15,333,0
Total   2.005.050   4.654.465   2.376.835   4.034.000   3.747.500   2.005.000   4.265.000   4.200.500   4.	Total		2,095,050	1,654,165	2,376,835	4,031,000	3,717,500	3,085,000	1,265,000	1,139,500	15,333,

Department: KPU Electric Project Priority: 1 Project Number:

600,000

600,000

Project Title: Beaver Falls Project Relicensing

Start Date:
01/18
Estimated Project Cost:
Design

Description: Land/Right-of-Way

during the consultation process.

The Beaver Falls Hydroelectric Project is licensed through the Federal Energy Regulatory Commission (FERC) for a term of 30 years. KPU's current license expires in 2024. To renew its FERC license, KPU began the process in 2018 with development of a Preliminary Application Document (PAD), with Notice of Intent (NOI) that was filed in 2019. Following NEPA and tribal consultations, and completion of studies, a final license application is due in 2022. This process will require professional services for FERC regulatory work, studies and surveys. Relicensing costs are highly variable and are dependent upon issues that arise

		<i>A</i>	Adopted 202	1		Projected R	equirement	S	
Fund	l Prior	Reappro-	New						Total
Source of Funds No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	443,000	80,000	40,000	120,000	37,000				600,000
Total	443,000	80,000	40,000	120,000	37,000				600,000

Division: Electric	Project Priority:	2	Project Number:	
Project Title: Warehouse Roof Repair and Replacement	Start Date: End Date:	01/20 12/21	Estimated Project Cost: Design	50,000
<b>Description:</b> The metal roof at the division headquarters warehouse leaks in n	nultiple locations during hea	avv rain events and sweats	Land/Right-of-Way Construction Management	·
with condensation during the winter. The water damages stored includes insulation batting and walls, along with channeling to a roof has been coated as a repair sometime in 1997. This coating	l material and structures w nd through boxed stock, fil	rithin the warehouse which es, etc. The existing metal	Construction Equipment Other	220,000
extensive roof replacement will be necessary.	, 2		Project Total	270,000

				Adopted 202	1		Projected R	equirement	s	
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund		50,000	120,000	100,000	220,000					270,000
Total		50,000	120,000	100,000	220,000					270,000

**Project Title:** Bailey Unit No. 3 Rehabilitation **Start Date:** 01/19

End Date: 12/21

### **Description:**

Bailey Generator No. 3 (BAG3) is a Colt-Pielstick (Fairbanks Morse), which was built in 1975. During operation in November 2018, the unit suffered a piston failure. The unit has had multiple piston failures as it ages due to the piston design. The unit was temporarily repaired with a spare piston/liner. Factory representatives from Fairbanks Morse conducted a site visit to evaluate reliability and recommended upgrading to a new more robust piston design that will prevent these types of failures. In 2019, new pistons, connecting rods and liners were purchased for \$500,000. New funding is required for the installation of the new parts. The upgrade will result in a more reliable unit, which should reduce excessive lubricating oil consumption and eliminate the unit's derating. This project will fund the piston upgrade and will allow for the additional upgrade of fuel delivery and monitoring components. COVID-19 delayed the parts delivery in 2020. KPU will competitively seek a qualified contractor in 2021 to install the new components and assist KPU with recommissioning BAG3.

# Project Number:

**Estimated Project Cost:** 

Design

Land/Right-of-Way

**Construction Management** 

Construction 400,000 Equipment 500,000

Other

Project Total 900,000

		Adopted 2021			Projected Requirements				
Fu	nd Prior	Reappro-	New						Total
Source of Funds N	o. Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	500,000	400,000		400,000					900,000
Total	500,000	400,000		400,000					900,000

**Project Title:** Bailey Unit No. 1 Rehabilitation **Start Date:** 01/19

End Date: 12/21

**Description:** 

Bailey Generator No. 1 (BAG1) was built in the 1970s. During operation in October 2018, BAG1 suffered a main bearing failure, which caused extensive damage to the powertrain. This project will fund the rehabilitation of the turbocharger, fuel delivery system and engine components including injectors, main journals, crankshaft, connecting rods, pistons, bearings and related components. The estimate assumes onsite work. The project may require additional funding if overhaul or repair of major components is not feasible or possible.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

**Construction Management** 

Construction 325,000 Equipment 540,835

Other

Project Total 865,835

		Adopted 2021 Projected Requirem				equirement	s		
Fur	d Prior	Reappro-	New						Total
Source of Funds No	. Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	15,835	834,165	15,835	850,000					865,835
Total	15,835	834,165	15,835	850,000					865,835

**Project Title:** Diesel Generation Modernization **Start Date:** 01/19

End Date: 12/21

### **Description:**

Maintaining reliable diesel generation capacity for times of high-loads, low reservoir levels and hydroelectric and transmission-line outages is extremely important for the integrity of Ketchikan's electrical grid. An architecture and engineering consultant specializing in diesel generation and facilities will be hired to evaluate KPU's existing diesel generation capabilities at Bailey Power Plant and North Pt. Higgins Substation Generation. The evaluation will identify and recommend solutions for existing and future reliability. Items to address include limitations and vulnerabilities of the existing infrastructure; determination of what is needed for existing redundancy; evaluation of future system growth without the immediate ability to add new hydropower or other power sources; and recommendations for solutions and options encompassing additional diesel generation capacity, locations, fuel supplies, air quality permits, conceptual designs and budgetary estimates for detailed design and construction options of those solutions.

**Project Number:** 

**Estimated Project Cost:** 

Design

Land/Right-of-Way

**Construction Management** 

Construction Equipment

Other 180,000

Project Total 180,000

			<i>A</i>	Adopted 202	1		Projected R	equirement	S	
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund		120,000	60,000		60,000					180,000
Total		120,000	60,000		60,000					180,000

Division: Electric	Project Priority:	6	Project Number:	
Project Title: Beaver Falls Switch Gear Replacement	Start Date: End Date:	01/17 12/22	Estimated Project Cost: Design/License	90,000
Description:	2.10 20101		Land/Right-of-Way	,
The Beaver Falls powerhouse switchgear needs replace existing equipment is 1940's vintage and beyond its rematerials, which will need to be abated during the replacement/upgrade of the three (3) generator excitation panels, DC electrical equipment and modification of the established scope of work and detailed work schedule, years and requires engineering services, planning, plandemolition/installation of equipment and commissioning.	liable life. It has been iden eplacement of the equipme n systems, controls, breaker he control room. This is This project will be compl	ntified as containing asbestos ent. This work requires the rs, protection relays, electrical a major project requiring an leted in phases over multiple	Construction Management Construction Equipment Other  Project Total	10,000 400,000 1,000,000 140,000

		Adopted 2021			Projected R	equirements			
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	105,000	35,000	1,500,000	1,535,000					1,640,000
Total	105,000	35,000	1,500,000	1,535,000					1,640,000

Department: KPU Electric Project Priority: 7

**Project Title:** Generator Rewind & Repair Start Date: 01/22

End Date: 12/23

**Description:** 

Typical life expectancy for generator windings is 30-40 years. Generators in service beyond 50 years become a major concern. They are at an elevated risk of failure causing loss of generation and/or potential powerhouse fires. This budget is to provide funding for two rewinds and other repairs as identified through testing and inspection.

Silvis: Unit No. 1 (1968)

Beaver Falls: Unit No. 1 (2014), Unit No. 3 (2018, and Unit No. 4 (2018) Ketchikan: Unit No. 3 (2015), Unit No. 4 (1951), and Unit No. 5 (1991)

# Project Number:

**Estimated Project Cost:** 

Design

Land/Right-of-Way

**Construction Management** 

Construction 850,000 Equipment 500,000

Other

Project Total 1,350,000

			P	Adopted 202	1		Projected Re	equirements	<b>;</b>	
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund						650,000	700,000			1,350,000
Total						650,000	700,000			1,350,000

Division: Electric Project Priority: 8 Project Number:

Project Title: Whitman Tailrace Modification Start Date: 01/20 Estimated Project Cost: End Date: 12/21 Design

Description: 12/21 Description:

The Whitman Hydroelectric Project operates under a FERC license, which requires monitoring of the tailrace that has shown fish to be stranded during normal operations. Operational adjustments have not been adequate to eliminate fish stranding. In 2019, KPU made modifications to the tailrace channel and continues to monitor it. Additional structural modifications may be necessary, the nature of which are subject to

consultation and approval by fisheries management agencies and FERC

Land/Right-of-Way
Construction Management

Construction 36,291 Equipment

Other

Project Total 36,291

			Adopted 2021 Projected Requirements							
F	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund		11,291		25,000	25,000					36,291
Total		11,291		25,000	25,000					36,291

Division: Electric Project Priority: 9 Project Number:

Project Title:Ketchikan Lakes UndergroundStart Date:01/22Estimated Project Cost:

**End Date**: 12/22 Design **Description**: Land/Right-of-Way

This project provides funding to install underground power & communications to Fawn Lake, Ketchikan Lakes and to the Granite Basin area, which will include approximately 7,500 linear feet of trenching, conduit, conduit elbows, pull boxes, sectionalizing cabinets, primary conductor, transformers, fiber, etc. Currently power at these sites is provided by solar panels with small back-up generators; with communications limited to line of

reet of trenching, conduit, conduit fiber, etc. Currently power at Construction Equipment Other

Construction Management

site antennas.

Project Total

250,000

			1	Adopted 202	1		Projected R	equirements	S	
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						250,000				250,000
Total						250,000				250,000

Division: Electric	Project Priority:	10	Project Number:	
Project Title: Ketchikan Tunnel Penstock Valves Replacement	Start Date:	01/13	Estimated Project Cost:	
	End Date:	12/23	Design	70,000
Description:			Land/Right-of-Way	
The three gets valves on the paretasks at the downstream	a and of the Katahikan newer tunn	al are old and are	Construction Management	
The three gate valves on the penstocks at the downstream nearing the end of their reliable service life. They must be ca			Construction	180,000
safety. The valves are embedded in concrete and will be diffic			Equipment	50,000
tunnel provides the City's only potable water supply, it cannot			Other	
and replacement of the valves will be coordinated with the Wa between Ketchikan Lakes and the city.			Project Total	300,000
				ļ

		Adopted 2021							
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	50,000				50,000	200,000			300,000
Tital	50.000				50.000				222.222
Total	50,000				50,000	200,000			300,000

Division: Electric	Project Priority:	11	Project Number:	
Project Title: Ketchikan International Airport				
and Pennock Island Upgrade	Start Date:	01/12	Estimated Project Cost:	
	End Date:	12/24	Design/License	50,000
Description:			Land/Right-of-Way	
The existing armored submarine electrical cable	that serves the airport is nearing the er	nd of its useful life (installed	Construction Management	
mid-1970's). The armoring has also begun to co	orrode, leading to the installation of slip-	on armoring on its Gravina	Construction	400,000
beach landing. The cable originates behind the	Bailey tank farm and runs through the a	rea of Vigor, Taquan,	Equipment	260,000
Carlanna Creek and the Bailey fuel barge delive cable. Design and specifications have been dev			Other	·
new armored cable beginning at a location near 2020. The submarine cable will be purchased ir programmed for installation in 2022 as the State	n 2021, along with continued uplands wo	ork. The new cable is	Project Total	710,000

		Adopted 2021			Projected Requirements				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	245,000		50,000	50,000	140,000	250,000	25,000		710,000
Total	245,000		50,000	50,000	140,000	250,000	25,000		710,000

**Project Priority: Division:** Electric 12 Project Number: Project Title: Downtown Underground Upgrade Estimated Project Cost: Start Date: 01/12 Design **End Date:** 12/24 75,000 Land/Right-of-Way Description: Construction Management Funding provides small scale tasks & upgrades as they become identified, as well as for the purchase of spare Construction 100,000 equipment & parts, including, but not limited to: Equipment 210,000 - Conductor Other 459 - Submersible transformers Project Total 385,459 - Switch gear - Pumps

- Vault lids

- Nearby overhead & adjoining overhead infrastructure (e.g. take-off poles & risers)

		Adopted 2021							
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund	310,459				25,000	25,000	25,000		385,459
Total	310,459				25,000	25,000	25,000		385,459

**Department:** Electric **Project Priority:** 13 Project Number: **Project Title:** Silvis Substation Upgrade Estimated Project Cost: **Start Date:** 01/20 End Date: 12/21 Design **Description:** Land/Right-of-Way Construction Management 125,000 In 2018 and 2019, KPU purchased new substation equipment for the Silvis substation including a Construction transformer, distribution switch, breaker and relays. KPU will competitively seek a qualified contractor in Equipment 2021 to provide auxiliary substation equipment and structures, site reconfigurations, oil containment Other repairs/upgrade, fencing, installation of the new KPU provided equipment and to assist KPU with Project Total 125,000 recommissioning the substation.

		Adopted 2021							
Fund	l Prior	Reappro-	New						Total
Source of Funds No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund		125,000		125,000					125,000
Total		125,000		125,000					125,000

**Project Title:** AMI, Meters and Meter Replacement Parts **Start Date:** 01/21

End Date: 12/25

**Description:** 

The division continues phasing in the AMI meters to make available advanced metering functions, including automated billing. This project also funds replacement of the division's metering equipment and AMI software & hardware. This project also funds validating metering system accuracy and replacement of residential and commercial meters that are on a 20 year replacement schedule (or 5% per year).

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 625,000

Other

Project Total 625,000

			Adopted 2021				Projected Requirements				
	Fund	Prior	Reappro-	New						Total	
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund				65,000	65,000	185,000	125,000	125,000	125,000	625,000	
Total				65,000	65,000	185,000	125,000	125,000	125,000	625,000	

Project Title: Transformer PurchaseStart Date:01/21End Date:12/25

Description:

This capital account funds the routine and preventative replacement and upgrades of both pole mounted and pad mounted transformers throughout the system. Projected increases are anticipated due to the expected rise in the price of metals.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 475,000

Other

Project Total 475,000

		Adopted 2021							
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			85,000	85,000	90,000	95,000	100,000	105,000	475,000
Total			85,000	85,000	90,000	95,000	100,000	105,000	475,000

**Project Title:** Battery Systems and Chargers Start Date: 01/20

End Date: 12/25

**Description:** 

There are ten battery systems and chargers throughout the KPU system within powerhouses and substations. Eight will be approaching end of life over the next ten (10) years. A battery system and charger failure will compromise system reliability. This project will start systematically replacing these systems. 2021 funding will replace one of these systems.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 264,500

Other

Project Total 264,500

			Adopted 2021			Projected Requirements				
Fi	nd Prior	Reappro-	New						Total	
Source of Funds N	o. Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund	17,000		19,000	19,000	56,000	76,000	46,000	50,500	264,500	
Total	17,000		19,000	19,000	56,000	76,000	46,000	50,500	264,500	

Division: Electric Project Priority: 17 Project Number:

Project Title: Bailey Fuel Tank PaintingStart Date:01/22End Date:12/22

Description:

Bailey 210,000 gallon fuel tank pressure wash, prep and painting. The tank is approximately 32 feet tall and 30' in

diameter.

Design
Land/Right-of-Way
Construction Management
Construction
Equipment 100,000

Estimated Project Cost:

Other
Project Total 100,000

		Adopted 2021			Projected R	equirements			
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund					100,000				100,000
Total					100,000				100,000

Department: k	(PU Electric	Project Priority:	18	Project Number:	
Project Title:	Bailey Mooring Dolphin Replacement	Start Date: End Date:	01/18 12/22	Estimated Project Cost: Design	30.000
is of wood pile	ed to the Bailey Power Plant by barge. On construction and at the end of its useful life nclude installation of the new dolphin, rened costs.	e. This project will replace it	t with a steel pile cluster.	Land/Right-of-Way Construction Management Construction Equipment Other	80,000
				Project Total	110,000

			Adopted 2021							
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						110,000				110,000
Total						110,000				110,000

**Project Priority: Division:** Electric **Project Number:** 19 Project Title: Operating Equipment **Start Date:** 01/21 **Estimated Project Cost: End Date:** 12/25 Design Land/Right-of-Way Description: Construction Management This capital account provides for the purchase of new or replacement equipment used for the operation and maintenance of Construction electrical service. Equipment 1) SCADA Critical Parts 15,000 1,463,500 2) Substation and Powerhouse Electronic Meters. Relays and Control Eq. 20,000 Other 3) New Test/Indication/Recorder Equipment, Repair & Recalibration 25,000 Project Total 1,463,500 4) Meters, Probes, Hand Tools, Radios 20,000 5) Customer Current & Potential Transformers 40,000 6) Generation and Powerhouse Spare Parts 50.000 7) Recording Equipment 10,000 8) NovaTech RTU Upgrade Orion 5R to Orion LX (Qty. 4) 15,000 9) Spare Powerhouse Generator Breakers 10,000 10) Control Equipment Upgrades 20.000 11) Communication and Control Cable Rreplacement-Upper Silvis Lake to Powerhouse 10,000 12) Data Radio Upgrade - RipEX 20,000 13) Capacitor Bank Control Upgrades and Parts 8,000

		Adopted 2021			Projected Re				
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund			263,000	263,000	375,500	275,000	275,000	275,000	1,463,500
Total			263,000	263,000	375,500	275,000	275,000	275,000	1,463,500

Division: Electric Project Priority: 20 Project Number:

Project Title: Vehicles & Moving Equipment Start Date: 01/22 Estimated Project Cost:

**End Date:** 12/25

**Description:** 

2022 Purchases:

Replace #185-44 1-ton dumpbed truck with new F-450 equivalent \$90,000

Replace #185-57 3/4-ton pick-up and 185-80 work van with new 3/4-ton pick-up with utility camper \$75,000

Projections:

2023:

Replace #183-55/57 mini-excavator with new 75-85 sized mini-excavator \$125,000

Replace #185-11 digger/derrick boom truck \$350,000

2024:

Replace #185-59 large bucket truck \$300,000

Replace small work truck(s)/van(s) \$80,000

2025:

Replace small work truck(s)/van(s) \$90,000

Replace small work truck(s)/van(s) \$100,000

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 1,210,000

Other

Project Total 1,210,000

		Adopted 2021							
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund					165,000	475,000	380,000	190,000	1,210,000
Total					165,000	475,000	380,000	190,000	1,210,000

Division: Electric Project Priority: 21 Project Number:

Project Title: Additional Projects
Start Date: 01/21
End Date: 12/25

Description:

This project represents funds for materials and labor for unidentified jobs that the division will be called upon to perform in 2021. Examples of additional projects include the installation of new transformers and banks of transformers, upgrading existing transformers and banks and upgrading secondary lift poles. These non-reimbursable projects are O&M in nature but are capital since they represent new installations.

Estimated Project Cost:
Design
Land/Right-of-Way
Construction Management

Construction

Equipment Other

Project Total 820,000

820,000

		Adopted 2021							
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			164,000	164,000	164,000	164,000	164,000	164,000	820,000
Total			164,000	164,000	164,000	164,000	164,000	164,000	820,000

Division: Electric	Project Priority:	22	Project Number:	
Project Title: Bailey Exhaust Stack Re-Coating	Start Date: End Date:	01/22 12/23	Estimated Project Cost: Design/License	25,000
Description:			Land/Right-of-Way	
This project is to sandblast and paint all four Bailey d corrosion coating. These efforts will mitigate further coand/or replacement. Work in 2022 will include development at the work in 2023	orrosion that may otherwise lead	to eventual high cost repairs	Construction Management Construction Equipment Other	225,000
·			Project Total	250,000

		Adopted 2021				Projected Requirements					
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project		
Revenue Generating Fund					25,000	225,000			250,000		
Total					25,000	225,000			250,000		

Division: Electric Project Priority: 23

Project Title: Reimbursable Projects
Start Date: 01/21
End Date: 12/25

Description:

This capital account represents funds for materials for work that the division will be called upon to perform at the request of outside agencies and customers. Examples of reimbursable projects are new line extensions and damage repairs to the electrical system resulting from accidents, negligence and vandalism. The division's expectation is that such work will be reimbursed 100%. This CIP provides a means for warehouse inventory and transformer accounts to be replenished due to customer projects.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 550,000

Other

Project Total 550,000

		Adopted 2021				Projected Ro	equirements		
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			25,000	25,000	150,000	125,000	125,000	125,000	550,000
Total			25,000	25,000	150,000	125,000	125,000	125,000	550,000

**Division:** Electric **Project Priority:** 24

**Project Title:** 34.5 kV Breaker and Relay Spares **Start Date:** 01/23

End Date: 12/25

Description:

34.5kV (38kV) Recloser with control cables and controller are used in the transmission system and

substation. These are critical components for system sectionalizing and isolation.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 155,000

Other

Project Total 155,000

			Adopted 2021				Projected R	equirements	6	
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund							50,000		105,000	155,000
Total							50,000		105,000	155,000

Division: Electric	Project Priority:	25	Project Number:			
Project Title: Bailey Generator Radiator Replacement	Start Date: End Date:	01/21 12/22	Estimated Project Cost: Design/License	25,000		
Description:			Land/Right-of-Way Construction Management	·		
requiring cutting and removing parts of the radiator system maintenance of the cooling system may result in the ever	The exterior radiators for Bailey Generator No. 3 (BAG3) and No. 4 (BAG4) continually develop leaks in the core, requiring cutting and removing parts of the radiator system. Increased generator usage and subsequent increased maintenance of the cooling system may result in the eventual need for complete radiator replacement. It may be possible to design a more cost effective solution in lieu of complete replacement.					
			Project Total	325,000		

		Adopted 2021				Projected R	equirements		
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Source of Fullus	Tears	priateu	Fulluling	TOLAI	2022	2023	2024	2025	Project
Revenue Generating Fund			25,000	25,000	300,000				325,000
Total			25,000	25,000	300,000				325,000

Division: Electric	Project Priority:	26	Project Number:	
Project Title: Beaver Falls Powerhouse Exterior	Start Date: End Date:	01/13 12/22	Estimated Project Cost: Design	10,000
Description:  The exterior of the Beaver Falls Powerhouse, which we Signs of water intrusion into the concrete walls and structure of the building structure and applications of the building structure.	cture are apparent. This pro	oject will entail an engineering	Land/Right-of-Way Construction Management Construction Equipment	626,070
evaluation of the building structure, an environmental er removal and disposal, concrete/structural repairs, a new		•	Other Project Total	636,070

		Adopted 2021				Projected R	equirements		
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	36,070				600,000				636,070
Total	36,070				600,000				636,070

Division: Electric	Project Priority:	27	Project Number:	
Project Title: Beaver Falls Governor Upgrade	Start Date: End Date:	01/23 12/23	Estimated Project Cost: Design	
Description:  KPU's hydro systems lack provision for isochronous o sometimes occurs during outages and restoration. This p isoc/droop governor operation for Beaver Falls Nos. 3 & 4.	peration (precise frequency contro	l) if islanded, as	Land/Right-of-Way Construction Management Construction Equipment	250,000
			Other Project Total	250,000

		Adopted 2021							
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						250,000			250,000
Total						250,000			250,000

**Department:** Electric **Project Priority:** Project Number: 28 **Project Title:** Bailey Generator No. 4 Wartsila PLC Estimated Project Cost: **Start Date:** 01/22 Upgrade End Date: 12/22 Design Land/Right-of-Way **Description:** Construction Management 115,000 The BAG4 PLC and I/O hardware are past end of life and beyond legacy support. This project will update the Construction generator to a modern PLC and I/O hardware platform. This project will be completed in phases and requires Equipment engineering services, planning, plans and specifications, the procurement of equipment, the Other demolition/installation of equipment, factory acceptance testing (FAT) and commissioning. Project Total 115,000

			Adopted 2021				Projected R	equirements	S	
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						115,000				115,000
Total						115,000				115,000

**Project Priority: Division:** Electric 29 Project Number: Estimated Project Cost:

Project Title: Vehicle Lift Replacement **Start Date:** 01/22 **End Date:** 12/22

Land/Right-of-Way Description: The existing stationary 4-post vehicle lift has a capacity of 12,000 pounds, while many of the 1-ton bucket trucks weigh 18,000 pounds. The intent is to purchase a set of four (4) mobile wheel lifts with a capacity of at least 20,000 Construction

pounds.

Equipment 80,000 Other

Design

Project Total 80,000

			Adopted 2021			Projected Requirements			
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund					80,000				80,000
Total					80,000				80,000

Division: Electric Project Priority: 30

Project Title: Generation Equipment Planning, Cleaning & Testing
Start Date: 01/14
End Date: 12/23

Description:

This project provides for comprehensive tests and evaluation of generator stator, rotor windings and generator related equipment. Detailed cleaning and generator repairs are necessary. Due to the scope of this work and required equipment, contracted work may be necessary. This work is essential in developing an updated plan for future rewinds and other major generator work. This budget is to provide funding for generator planning activities, cleaning, testing and required equipment in the KPU generation system.

Project Number:

Estimated Project Cost:

Design/License Land/Right-of-Way

Construction Management

Construction Equipment

Other 291,395

Project Total 291,395

		Adopted 2021				Projected Re	equirements		
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	191,395				50,000	50,000			291,395
Total	191,395				50,000	50,000			291,395

## Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program

**Division: Telecommunications** 

			Adopted 2021		F	rojected Re	equirement	S		
		Prior	Reappro-	New						Total
Project Title	Priority	Years	priated	Funding	Total	2022	2023	2024	2025	Project
REGULATED										
Normal Growth and Repair - Buildings	1			10,000	10,000	25,000	25,000	30,000	35,000	125,000
Normal Growth and Repair - CO Switching	2					500,000	150,000	100,000	50,000	800,000
Normal Growth and Repair - Copper Cable	3			10,000	10,000	20,000	20,000	20,000	25,000	95,000
Normal Growth and Repair - Fiber Cable	4			100,000	100,000	200,000	150,000	150,000	150,000	750,000
Normal Growth and Repair - CO Transmission	5			150,000	150,000	150,000	150,000	150,000	150,000	750,000
Normal Growth and Repair - Expansion	6			5,000	5,000	25,000	25,000	25,000	30,000	110,000
Normal Growth and Repair - Provisioning	7			10,000	10,000	50,000	150,000	100,000	50,000	360,000
Fiber to the Home	8			50,000	50,000	75,000	75,000	75,000	75,000	350,000
Remote Cabinets for Advanced Services	9			10,000	10,000	25,000	25,000	25,000	35,000	120,000
Core Network Upgrade	10			100,000	100,000	100,000	800,000	700,000	500,000	2,200,000
Server Environment	11			50,000	50,000	100,000	150,000	200,000	150,000	650,000
Multi-Dwelling Unit Project	12			100,000	100,000	200,000	200,000	200,000	200,000	900,000
Operating Equipment	13			15,000	15,000	50,000	60,000	60,000	65,000	250,000
PC Hardware & Software	14			40,000	40,000	45,000	50,000	50,000	55,000	240,000
Power Expansion/Reclamation	15			5,000	5,000	25,000	25,000	30,000	35,000	120,000
Visual Mapping Software	16					25,000	25,000	25,000	30,000	105,000
Network Monitoring	17			100,000	100,000	100,000	100,000	120,000	130,000	550,000
Vehicle Acquisition	18					100,000	100,000	150,000	150,000	500,000
Security	19						100,000	120,000	200,000	420,000
NON-REGULATED										
Headend Expansion	20			10,000	10,000	40,000	35,000	35,000	25,000	145,000
IPv4 Addressing	21					100,000	50,000	50,000		200,000
Video Set Top Boxes	22			25,000	25,000	50,000	25,000	25,000	10,000	135,000
4G/LTE	23			60,000	60,000	150,000	150,000	150,000	150,000	660,000
Microwave	24					25,000	25,000	25,000	25,000	100,000
Hosted	25			100,000	100,000	2,022	200,000	250,000	200,000	752,022
WiFi	26			50,000	50,000	50,000	75,000	75,000	100,000	350,000
Internet Expansion	27	10,425,000	1,175,000		1,175,000					11,600,000
Total		10,425,000	1,175,000	1,000,000	2,175,000	2,232,022	2,940,000	2,940,000	2,625,000	23,337,022

		Adopted 2021			Projected Requirements				
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund Revenue Bond	100,000 10,325,000	1,175,000	1,000,000	1,000,000 1,175,000	, - ,-	2,940,000	2,940,000	2,625,000	11,837,022 11,500,000
Total	10,425,000	1,175,000	1,000,000	2,175,000	2,232,022	2,940,000	2,940,000	2,625,000	23,337,022

Project Title:Normal Growth and Repair - BuildingsStart Date:01/21End Date:12/25

Description:

This capital account provides funding for improvements to existing buildings including HVAC improvements, replacement of lighting fixtures and installation of building alarms or related security items.

Project Number:

**Estimated Project Cost:** 

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 125,000

Other

Project Total 125,000

		Δ.	dopted 202	1	F	Projected Re	equirements	S	
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			10,000	10,000	25,000	25,000	30,000	35,000	125,000
Total			10,000	10,000	25,000	25,000	30,000	35,000	125,000

Project Title:Normal Growth and Repair - Central OfficeStart Date:01/21SwitchingEnd Date:12/25

Description:

This capital account provides funding for reliability upgrades and additional capacity equipment required for the division's telecommunications switching and voice over Internet protocol network. Included are funds to enhance least cost routing and fraud detection, as well as to ensure that features work with all residential lines.

Additionally, this budget item purchases one new softswitch to replace the end-of-life T7000 class 5 switch in 2022 to work in tandem with the Broadworks feature softswitch. This also includes funding to replace the ACME session border controllers with newer hardware and software to facilitate the protection of all of the division's ip voice platforms.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 800,000

Other

Project Total 800,000

	Adopted 2021			:1	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund					500,000	150,000	100,000	50,000	800,000
Total					500,000	150,000	100,000	50,000	800,000
i viai					500,000	150,000	100,000	50,000	000,000

Division: Telecommunications	Project Priority:	3	Project Number:	
Project Title: Normal Growth and Repair - Copper Cable	Start Date:	01/21	Estimated Project Cost:	2 200
Description:	End Date:	12/25	Design Land/Right-of-Way Construction Management	3,800
This capital account provides funding for the replacement of o	deteriorated cables and cons	struction of minor cable	Construction	38,000
projects, including line extensions. This capital account also furequired to reconnect to poles replaced by the Electric Division.	•	niscellaneous hardware	Equipment Other	53,200
			Project Total	95,000

		A	Adopted 202	1	F	Projected Re	equirement	S	
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			10,000	10,000	20,000	20,000	20,000	25,000	95,000
Total			10,000	10,000	20,000	20,000	20,000	25,000	95,000

Division: Telecommunications	Project Priority:	4	Project Number:	
Project Title: Normal Growth and Repair - Fiber Cable	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	15,000
Description:  This capital account provides funding for additional fiber optic fiber projects necessary for the efficient operation of the Utili labor for continued installation of fiber service drops for custo	ity. This capital account also	includes materials and	Equipment	412,500 322,500
areas served by the division's fiber cable network.	, and the second		Other Project Total	750,000

		_ A	dopted 202	1	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			100,000	100,000	200,000	150,000	150,000	150,000	750,000
Total			100,000	100,000	200,000	150,000	150,000	150,000	750,000

Project Title:Normal Growth and Repair - CO TransmissionStart Date:01/21End Date:12/25

**Description:** 

This capital account provides funding for the purchase and installation of additional intelligent Network Interface Devices (NIDS) and Optical Network Terminals (ONTS) required to deliver service to customers served via fiber optic cable. This capital account also includes funding for required/associated internal network fiber ports. Also included is funding for network transmission electronics necessary to serve business customers with new private line services including digital data service, optical wide area network, T1s, etc. This capital account also includes the funding to finish the migration off the division's legacy platforms, which are no longer supported, to the standard Adtran platforms for both Optical and VDSL services. In 2024 the Total Access Adtran platform will likely be end-of-life, so KPU will need to implement a new FTTH platform.

Project Number:

**Estimated Project Cost:** 

Design

Land/Right-of-Way

Construction Management

Construction 60,000 Equipment 690,000

Other

Project Total 750,000

		Α	dopted 202	:1	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			150,000	150,000	150,000	150,000	150,000	150,000	750,000
Total			150,000	150,000	150,000	150,000	150,000	150,000	750,000

Division: Telecommunications	Project Priority:	6	Project Number:	
Project Title: Normal Growth and Repair - Expansion	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	
Description:			Land/Right-of-Way	
This capital account provides funding to upgrade, maintain and reliable services are provided to underserved, outlying areas. T to provide services to remote areas.	expand the division's "off isl his project utilizes both wire	eless and fiber technologies	Construction Management Construction Equipment Other	22,000 88,000
			Project Total	110,000

			Adopted 2021		I	Projected Re	quirements		
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			5,000	5,000	25,000	25,000	25,000	30,000	110,000
-									
Total			5,000	5,000	25,000	25,000	25,000	30,000	110,000

Division: Telecommunications	Project Priority:	7	Project Number:	
Project Title: Normal Growth and Repair - Provisioning	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	97,200
Description:  This capital account provides funding for the introduction,	ungrade automation and	integration of evotome	Land/Right-of-Way Construction Management	
necessary to promote the enhancement of the customer ser begin to attempt to replace the division's trouble ticketing softw	vice and support experience	e. In 2023, an effort will	Software Equipment Other	190,800 39,600 32,400
			Project Total	360,000

		Α	dopted 202	1	ı	Projected R	equirements	3	
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			10,000	10,000	50,000	150,000	100,000	50,000	360,000
Total			10,000	10,000	50,000	150,000	100,000	50,000	360,000

Division: Telecommunications	Project Priority:	8	Project Number:	
Project Title: Fiber to the Home	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	8,750
Description:			Land/Right-of-Way	2, 22
This capital account provides funding for contract labor to to homes, businesses and multi-dwelling units throughout to look into providing fiber into outlying, underserved areas	Ketchikan. Additionally, this proje		er Construction	131,250 210,000
			Project Total	350,000

		Δ	dopted 202	1	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			50,000	50,000	75,000	75,000	75,000	75,000	350,000
Total			50,000	50,000	75,000	75,000	75,000	75,000	350,000

Division: Telecommunications	Project Priority:	9	Project Number:			
Project Title: Remote Cabinets for Advanced Services	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	3,000		
Description:	or raplacement of remote au	itahing aghinata (BSC)	Land/Right-of-Way Construction Management			
This project also equips RSC's with remote monitoring sensor	his capital account provides funding for the maintenance and/or replacement of remote switching cabinets (RSC). his project also equips RSC's with remote monitoring sensors, ensuring technicians can remotely detect proper peration prior to failure. This account also funds the out-of-band network back to the Central Office.					
			Project Total	120,000		

		A	dopted 202	1	Projected Requirements				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund		-	10,000	10,000	25,000	25,000	25,000	35,000	120,000
Total			10,000	10,000	25,000	25,000	25,000	35,000	120,000

Division: Telecommunications	Project Priority:	10	Project Number:	
Project Title: Core Network Upgrade	Start Date:	01/21	Estimated Project Cost:	
	End Date:	12/25	Design	110,000
Description:			Land/Right-of-Way	
This conital account provides funding for the expansion of the	a aviating care to add	additional regilional and	Construction Management	
This capital account provides funding for the expansion of the diversity to key components. Additionally, it will continue to fund			Construction	
in the remote sites, in order to provide additional bandwidth, al			Equipment	1,980,000
scale. This project also funds the distribution routers at ea			Other	110,000
connections where L3 routing components become necessary to and e-lan services to customers off-island. The current core of the on various types of hardware so there is an effort in 2023 to move	ne network goes end-of-	life 2023-2025 depending	Project Total	2,200,000

		A	Adopted 202	1	Projected Re		Requirements		
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			100,000	100,000	100,000	800,000	700,000	500,000	2,200,000
			100,000	400.000	100.000	222 222	700 000	500.000	0.000.000
Total			100,000	100,000	100,000	800,000	700,000	500,000	2,200,000

Division: Telecommunications	Project Priority:	11	Project Number:	
Project Title: Server Environment	Start Date:	01/21	Estimated Project Cost:	
	End Date:	12/25	Design	16,250
Description:			Land/Right-of-Way	
This conital account provides funding for the growth expan	soion and ungrade of the divi	ision's data storage and	Construction Management	
This capital account provides funding for the growth, expan virtualized server environment. This allows the division to sta			Construction	16,250
physical footprint and reducing overall power consumption.			Equipment	617,500
VM technology to supplement the division's hosted datacente	er service offerings and offer o	loud based services.	Other	
			Project Total	650,000

			Adopted 2021			Projected Requirements				
	Prior	Reappro-	New						Total	
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund			50,000	50,000	100,000	150,000	200,000	150,000	650,000	
Total			50,000	50,000	100,000	150,000	200,000	150,000	650,000	

Division: Telecommunications	Project Priority:	12	Project Number:	
Project Title: Multi-Dwelling Unit Project	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	22,500
Description:			Land/Right-of-Way Construction Management	·
This capital account provides funding for the purchase of			Construction	22,500
of triple-play services to the 40% of KPU customers res the need to run multiple fibers into multi-dwelling unit			Equipment	855,000
install and maintain the per each fiber electronics require		corresponding need to	Other	000 000
			Project Total	900,000

			Adopted 202	:1	F	Projected Re	equirement	S	
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			100,000	100,000	200,000	200,000	200,000	200,000	900,000
Total			100,000	100,000	200,000	200,000	200,000	200,000	900,000

**Division:** Telecommunications **Project Priority:** 13 **Project Number:** 

Project Title: Operating EquipmentStart Date:01/21End Date:12/25

Description:

This capital account provides funding for the test equipment utilized by KPU technicians to test, repair and install high speed data and voice circuits, particularly as it relates to KPU's expanded fiber optic network and 4G networks.

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment 250,000

Other

Project Total 250,000

		-	Adopted 202	:1	Projected Requirements				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			15,000	15,000	50,000	60,000	60,000	65,000	250,000
Total			15,000	15,000	50,000	60,000	60,000	65,000	250,000

Project Title:PC Hardware and SoftwareStart Date:01/21End Date:12/25

**Description:** 

This capital account funds replacement of outdated computers (identified by the Information Technology Department for replacement) and purchases of new hardware and software for the network operations control center. Laptops, iPads, and desktop computers for troubleshooting/training out in the field or in the Central Office.

Project Number:

**Estimated Project Cost:** 

Design

Land/Right-of-Way

Construction Management

Construction

Equipment

laibinenr

Other

Project Total 240,000

240,000

		<i>p</i>	Adopted 202	21	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			40,000	40,000	45,000	50,000	50,000	55,000	240,000
-									
Total			40,000	40,000	45,000	50,000	50,000	55,000	240,000

**Division:** Telecommunications **Project Priority:** Project Number: 15 Project Title: Power Expansion/Reclamation Start Date: 01/21 Estimated Project Cost: End Date: 12/25 Design 3,000 Description: Land/Right-of-Way This capital account provides funding for the expansion of power facilities via new AC/DC filtering or reclamation of Construction Management existing usage via more efficient equipment. Construction 3,000 114,000 Equipment Other Project Total 120,000

		Δ.	Adopted 2021			Projected Requirements				
	Prior	Reappro-	New						Total	
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund			5,000	5,000	25,000	25,000	30,000	35,000	120,000	
Total			5,000	5,000	25,000	25,000	30,000	35,000	120,000	

Project Title: Visual Mapping Software Start Date: 01/21 End Date: 12/25

## Description:

This capital account provides funding to enhance the division's documentation and ability to automate and distribute inside and outside plant design at the physical and logical levels. Future funding procures enhancements and labor to ensure the system is properly audited and meeting the needs of division customers.

At some point in the future Telecom may need to purchase software outside of the City's mapping software that is specific to managing a fiber/copper network from end-to-end. This budget provides funding to investigate some of those options. This project was deferred for 2021

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

 Construction
 12,600

 Equipment
 38,850

 Other
 53,550

 Project Total
 105,000

		<b>A</b>	Adopted 2021			Projected Requirements				
	Prior	Reappro-	New						Total	
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund					25,000	25,000	25,000	30,000	105,000	
Total					25,000	25,000	25,000	30,000	105,000	

Project Title: Network Monitoring

Start Date: 01/21

End Date: 12/25

**Description:** 

This capital account provides funding for the purchase of hardware and software critical to enhance the monitoring and complete visibility of the KPU network for the purposes of resolving customer issues quickly and putting the network in a place where a variety of monitoring products can be deployed to identify threats.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

 Equipment
 192,500

 Other
 357,500

 Project Total
 550,000

		Δ	dopted 202	1	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			100,000	100,000	100,000	100,000	120,000	130,000	550,000
·									
Total			100,000	100,000	100,000	100,000	120,000	130,000	550,000

**Division:** Telecommunications **Project Priority:** 18 Project Number: Project Title: Vehicle Acquisition 01/21 **Estimated Project Cost:** Start Date: End Date: 12/25 Design Description: Land/Right-of-Way This capital account funds replacement of aging vehicles to prevent excessive maintenance costs and breakdowns Construction Management Construction

affecting KPU Telecom's ability to meet customer demands. All vehicle needs have been deferred to 2022.

Equipment 500,000 Other Project Total 500,000

			Adopted 202	21	P	Projected Requirements			
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund		_			100,000	100,000	150,000	150,000	500,000
-									
Total					100,000	100,000	150,000	150,000	500,00

Department: Telecommunications	Project Priority:	19	Project Number:	
Project Title: Security	Start Date:	01/21	Estimated Project Cost:	
	End Date:	12/25	Design	57,200
Description:			Land/Right-of-Way	
This capital account provides funding for the cexternal threats in detecting and preventing the	•		Construction Management Construction	
denial of service. Detecting and responding to	cyberattacks in real-time requires a spec	ialized set of analytical	Equipment	462,800
software to protect the network. This project i	s deferred for 2021.		Other	
			Project Total	520,000

			Adopted 2021							
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						100,000	100,000	120,000	200,000	520,000
Total										

Division: Telecommunications	Project Priority:	20	Project Number:	
Project Title: Headend Expansion	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	725
Description:			Land/Right-of-Way Construction Management	120
This capital account provides funding for the growth and char due to normal business growth and change. Additionally, this in the division's video delivery platform along with some encr	s project will fund increased re yption to protect content and	dundancy and diversity ensure compliance with	Construction Equipment	7,250 137,025
all regulatory bodies. Lastly, this capital account will fund efficiently distribute video.	d a conversion to MPEG-4,	allowing KPU to more	Project Total	145,000

		<i> </i>	Adopted 2021			Projected Requirements				
	Prior	Reappro-	New						Total	
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund			10,000	10,000	40,000	35,000	35,000	25,000	145,000	
Total			10,000	10,000	40,000	35,000	35,000	25,000	145,000	

**Department:** Telecommunications **Project Priority:** 21

**Project Title:** IPv4 Addressing Start Date: 01/21

End Date: 12/25

**Description:** 

This capital account provides funding for the continued growth and need for additional IPv4 addressing in the division's network. This account funds the purchase an additional 8,192 addresses in order to accommodate current needs and some future growth in 2022. This project has been deferred for 2021

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction Equipment

 Other
 200,000

 Project Total
 200,000

			Adopted 2021			ı	1			
	Fund	Prior	Reappro-	New		2222	2222	2224	222	Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						100,000	50,000	50,000		200,000
Total						100,000			<u>'</u>	

Project Title: Video Set Top BoxesStart Date:01/21End Date:12/25

Description:

This capital account funds the purchase of customer set top boxes (STB's) utilized in the provision of CommVision television service. This account also funds the purchase of Personal Video Recorders (PVRs) required to provide time shifted television.

Project Number:

Estimated Project Cost:

Design

Land/Right-of-Way

Construction Management

Construction

Equipment

Other

Project Total 135,000

135,000

		<i>p</i>	Adopted 202	<u>!</u> 1	F				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			25,000	25,000	50,000	25,000	25,000	10,000	135,000
Total			25,000	25,000	50,000	25,000	25,000	10,000	135,000

Division: Telecommunications	Project Priority:	23	Project Number:	
Project Title: 4G/LTE	Start Date:	01/21	Estimated Project Cost:	0.000
Description:	End Date:	12/25	Design Land/Right-of-Way Construction Management	6,600
This capital account provides continued funding to consaccount will fund the addition of a new site in Ward Cove.	struct and maintain KPU's 4G/LT	E Mobile network.	This Construction Equipment Other	99,000 554,400
			Project Total	660,000

			Adopted 2021			Projected Requirements				
	Prior	Reappro-	New						Total	
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund			60,000	60,000	150,000	150,000	150,000	150,000	660,000	
Total			60,000	60,000	150,000	150,000	150,000	150,000	660,000	

Division: Telecommunications	Project Priority:	24	Project Number:	
Project Title: Microwave	Start Date:	01/21	Estimated Project Cost:	
	End Date:	12/25	Design	1,000
Description:			Land/Right-of-Way	
			Construction Management	
This capital account provides continued funding	j to construct, expand and maintain KPU'	s microwave system to	Construction	15,000
Canada. Deferred for 2021			Equipment	84,000
			Other	
			Project Total	100,000

Source of Funds Revenue Generating Fund	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
	Years			Total		2023	2024	2025	Project
Revenue Generating Fund									, - , - , - , - , - , - , - , - ,
					25,000	25,000	25,000	25,000	100,000
Total					25,000	25,000	25,000	25,000	100,000

<b>Division:</b> Telecommunications		Project Price	ority:	25		Project Num			
Project Title: Hosted		Start Date:		01/21		Estimated P			
		End Date:		12/25					
Description:						Lab System			135,00
This capital account provides funding to upgrade, m	naintain and e	xpand busine	ess offerings o	n the divisio	n's Hosted	Jazz			135,00
Platforms.		•	J			Training			207,00
						Licenses			288,00
						Integration			135,00
						Project Total			900,00
			Adopted 2021			Projected Re	quirements		
	Prior	Reappro-	New			_	-		Total
Source of Funds Revenue Generating Fund	Prior Years		•	<b>Total</b> 100,000	<b>2022</b> 150,000	2023 200,000	2024 250,000	<b>2025</b> 200,000	Total Project

100,000

100,000

150,000

200,000

250,000 200,000

900,000

Total

Division: Telecommunications	Project Priority:	26	Project Number:	
Project Title: WiFi	Start Date: End Date:	01/21 12/25	Estimated Project Cost: Design	8,750
Description:			Land/Right-of-Way Construction Management	2,
This capital account funds the ability for KPU to deploy Wi WiFi services for local and transient customers. This account customers who are difficult to serve using wired connectivity	ınt also funds efforts to make W			70,000 271,250
			Project Total	350,000

			Adopted 2021		I				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			50,000	50,000	50,000	75,000	75,000	100,000	350,000
Total			50,000	50,000	50,000	75,000	75,000	100,000	350,000

Division: Telecommunications		Project Prior	ity:	27		Project Number:					
Project Title: Internet Expansion		Start Date:		01/19	Estimated Pro						
Descriptions	End Date: 12/21						Design				
Description:		Land/Right-of- Construction M	-								
This capital account provides funding for the grow						Construction	6,995,500				
transport networks providing broadband, wireless an	id iP i v conne	ction leeds to t	THE CIVISION S	non-regulated	customers.	Equipment 4,50			4,504,500		
						Other Project Total	11,600,000				
	т				1						
		1	Adopted 202	1		Projected Red	quirements				
	Prior	Reappro-	New						Total		

			Adopted 202	1	Projected Requirements				
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund - Growth	100,000								100,000
Revenue Bonds	10,325,000	1,175,000		1,175,000					11,500,000
Total	10.425.000	1.175.000		1.175.000					11.600.000

## Ketchikan Public Utilities 2021 - 2025 Capital Improvement Program

Division: Water

			Adopted 2021 Projected Requirements							
Project Title	Priority	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Project fille	Priority	Tears	priateu	runanig	าบเลา	2022	2023	2024	2025	Project
Water Filtration Facility Project	1	138,300	386,700		386,700					525,000
Schoenbar Raw Water Main (Charter School - Middle School)	2	427,000	7,092,499		7,092,499					7,519,499
Water Meters - Business & Commercial Customers	3	512,840	756,178		756,178					1,269,018
Federal Act - Risk & Resilience Assessment	4			150,000	150,000					150,000
SCADA PLC Controllers	5	50,000		260,000	260,000		265,000		285,000	860,000
Water Distribution Grid Improvements	6			30,000	30,000	30,000	30,000	30,000	30,000	150,000
Additional Projects	7			40,000	40,000	40,000	40,000	40,000	40,000	200,000
Water Service Upgrade Program	8			15,000	15,000	15,000	15,000	15,000	15,000	75,000
Backflow Prevention Program	9			15,000	15,000	15,000	15,000	15,000	15,000	75,000
Highlands Reservoir Property Acquisition	10							270,000		270,000
Second Avenue Utility Improvements	11					15,000			1,300,800	1,315,800
West Fairy Chasm Utility Improvements	12					15,000			550,600	565,600
Skyline Water Main Replacement	13					10,000			360,800	370,800
Denali Ave. Utility Improvements	14					15,000			512,000	527,000
Evergreen Ave. Utility Improvements	15					15,000			440,000	455,000
Utility Vehicles	16					37,500	118,000	94,000		249,500
Total		1,128,140	8,235,377	510,000	8,745,377	207,500	483,000	464,000	3,549,200	14,577,217

		Adopted 2021				Projected Requirements				
	Prior	Reappro-	New						Total	
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project	
Revenue Generating Fund	263,300	386,700	510,000	896,700	207,500	483,000	194,000	385,000	2,429,500	
Revenue Bonds - ADWF Loan	864,840	7,848,677		7,848,677			135,000	1,582,100	10,430,617	
Proposed State 50% Municipal Assistance Funding							135,000	1,582,100	1,717,100	
	1,128,140	8,235,377	510,000	8,745,377	207,500	483,000	464,000	3,549,200	14,577,217	

Department: Water Project Priority: 1 Project Number: 5400 2019 007

Project Title: Filtration Facility - Preliminary Preparation TasksStart Date:01/20Estimated Project Cost:

End Date: 12/21 Design Land/Right-of-Way

**Description:** 

During October 2019, Ketchikan's water system violated Federal Regulation CFR 141.71 as it applies to unfiltered water systems, which resulted in ADEC issuing notice that KPU enter a Compliance Order by Consent to begin Ketchikan's construction of a modern filtration system. The Safe Drinking Water Act Amendments of 1996 provide a Limited Alternative to Filtration (LAF) regulatory pathway for water systems like the City of Ketchikan's to remain unfiltered even with raw water coliforms above the limits as long as the delivered water meets all regulatory requirements for potable water. While the City and ADEC will continue to work with EPA to reach a non-filtration solution, if a regulatory pathway to save Ketchikan from installing costly filtration cannot be achieved, the City will be required to further develop plans for a filtration facility. This project will fund the continued professional services efforts of contractor Jacobs Engineering Group as the City navigates a non-filtration solution that meets regulatory requirements.

Construction Management
Construction
Equipment
Other 525,000

525,000

Project Total

				Adopted 202	1		Projected R	equirements	3	
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund		138,300	386,700		386,700					525,000
Total		138,300	386,700		386,700					525,000

Division: Water Project Priority: 2

Project Title: Schoenbar Water Mains (Charter School - Middle School)

Start Date:
01/18
End Date:
12/21

**Description:** 

DOWL Engineers, who have already completed the earlier design work for replacement of Schoenbar Road's distribution water & sewer mains, are now designing a replacement for the portion of the failing 36-inch ductile iron main in Schoenbar Road located between the westerly edge of Norman Walker Field and the Ketchikan Charter School. Their initial analysis determined that a single permanent, buried 42-inch HDPE pipeline generally aligned along the west side of Schoenbar Road under the existing sidewalk was the most cost-effective route between the Schoenbar Middle School and the Ketchikan Charter School. As their design progressed they encountered a number of physical challenges that caused DOWL to question the feasibility, the risks, and the resulting additional costs that would be necessary to construct the 42-inch HDPE pipeline along this proposed route. Instead, authorization was sought from the City Council to seek property easements for the proposed alternative alignment over to the west and away from Schoenbar Road itself. The proposed route now passes beneath the Ketchikan Charter School playground, the driveways of the School District Maintenance Shop and Schoenbar Middle School before terminating near the southeasterly edge of Norman Walker Field.

Project Number: Comb 2019 001

**Estimated Project Cost:** 

Design

Land/Right-of-Way

Construction Management

Construction 6,857,099

Equipment

Other (Loan Subsidy) 662,400

Project Total 7,519,499

			Adopted 202	1		Projected R	equirements	S	
	Prior	Reappro-							Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund Revenue Bonds - ADWF Loan	427,000	7,092,499		7,092,499					7,519,499
Total		7,092,499		7,092,499					7,519,499

Department: Water	Project Priority:	3	Project Number: Comb 2018 001	I
Project Title: Water Meters - Business &				
Commercial Customers	Start Date:	01/18	Estimated Project Cost:	
	End Date:	12/22	Design	75,000
Description:			Land/Right-of-Way	
Metering commercial water and wastewater of loan offer from the Alaska Department of Environment and installation of water meters of business customers. Approximately 125 meters another 50 meters is in progress. As before,	rironmental Conservation, a bond has be the premises of Ketchikan's approxing rs are already installed and another design this contract is limited in size to allow of	een issued to finance the mately 450 commercial & ign/build contract to install everyone involved to both	Construction Equipment Other Project Total	1,194,018 1,269,018
gain experience and to obtain better knowledgemeters. If this proves to be a satisfactory method be advertised. Achieving the goal of having all apartment complexes buildings fully metered by approximately 265 unmetered businesses a Wastewater Rate Study will need to be updated \$2,150,000 is needed and will be shared equated for in their respective enterprise funds.	nod to install water meters, subsequent I of these business and commercial build efore the end of 2021 will require signific nd large apartment complexes. In a ed and the new metered rates adopted	design-build contracts will dings and large residential cant effort as there are still ddition, the 2016 Water/ d. A capital investment of		1,209,010

		Adopted 2021				Projected R	equirements	3	
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund Revenue Bonds - ADWF Loan	75,000 437,840	756,178		756,178					75,000 1,194,018
Total	512,840	756,178		756,178					1,269,018

Division: Water Project Priority: 4 Project Number:

Project Title: Federal Act - Risk & Resilience Assessment Start Date: 01/21 Estimated Project Cost:

End Date: 12/21 Design

Description:

Recently adopted Federal Regulations in the America's Water Infrastructure Act require every community water system to complete a new Risk and Resilience Assessment (RRA) and develop an Emergency Response Plan (ERP). Although KPU developed one in the aftermath of 911 and has kept it updated, this legislation includes additional specific requirements particularly in the electronic/cyber security and malevolent act detection fields. Due by June 30, 2021, the RRA requires evaluation of the risk to the system from malevolent acts, natural hazards, the resilience and security of our distribution system, monitoring practices, use and storage of chemicals, and financial infrastructure to support management of the system. Similarly, the ERP due by December 31, 2021 incorporates the findings of the RRA and includes strategies to improve system resilience, plans & procedures to respond to malevolent acts or natural hazards, as well as procedures or equipment that can be used to aid in the detection of malevolent acts or hazards that threaten the security of the water system.

Land/Right-of-Way
Construction Management
Construction
Equipment
Other
Project Total

Land/Right-of-Way
Construction
Equipment
Other
150,000

150,000

			4	Adopted 202	1		Projected R	s		
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund				150,000	150,000					150,000
Total				150,000	150,000					150,000

**Department:** Water Project Priority: 5

**Project Title:** SCADA PLC Controllers **Start Date:** 01/19

End Date: 12/25

**Description:** 

Collectively, KPU has three Allen-Bradley Programmable Logic Controllers (PLCs) installed at the UV Facility, the Chlorination Plant, and the Ammonia Addition Facility. They are each providing continuous supervisory control over specific critical components within KPU's complex, computer-controlled, disinfection process. This version of Allen Bradley PLCs, which were introduced in 2005, are expected to cease receiving any further factory support within the next couple of years. This includes no longer maintaining any inventory of spare parts or the necessary input/ output (I/O) modules. One PLC is located at the Water Treatment UV Facility (CP-100), another at the Old Chlorination Building (CP-300), and the third in the Ammonia Building (CP-400). The approach is to migrate to the Allen-Bradley ControlLogix PLC platform and split the replacements into three phases spread over several years beginning with CP-100. However, due to the negative impact that coronavirus has had upon the City's finances in 2020, it was deferred and removed from the 2020 Budget. It is now proposed to begin in 2021.

Project Number: 5400 2020 006

**Estimated Project Cost:** 

Design 150,000

Land/Right-of-Way

Construction Management

Construction 525,000 Equipment 185,000

Other

Project Total 860,000

		Adopted 2021				Projected R	equirement	S	
Fur	d Prior	Reappro-	New						Total
Source of Funds No	. Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund	50,000		260,000	260,000		265,000		285,000	860,000
Total	50,000		260,000	260,000		265,000		285,000	860,000

Division: Water Project Priority: 6 Project Number:

Project Title:Water Distribution Grid ImprovementsStart Date:01/21End Date:12/25

d Date: 12/25 Design

Description:

Land/Right-of-Way

Each year in conjunction with the work of other agencies, the Water Division is presented with opportunities to undertake repairs to improve the municipal water system. This account provides the funding for such improvements.

Construction Management Construction

Equipment
Other

Project Total 150,000

150,000

		-	Adopted 202	1	F	3			
	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			30,000	30,000	30,000	30,000	30,000	30,000	150,000
Total			30,000	30,000	30,000	30,000	30,000	30,000	150,000

Division: Water Project Priority: 7 Project Number:

**Project Title:** Additional Projects **Start Date:** 01/21

End Date: 12/25 Design Land/Right-of-Way

Description:

This account provides for the cost of fire hydrants and other related materials, which are provided by the Utility in water line extensions and are then incorporated into the municipal water system. This account also provides a source of funds for repair Construction

extensions and are then incorporated into the municipal water system. This account also provides a source of funds for repair or installing new valve boxes in City streets when Public Works' annual repaving projects occur. Although specific streets have not yet been selected for asphalt paving in 2021, there will be paving scheduled for next year. This project has been an ongoing initiative of the division to make incremental improvements in cooperation with Public Works Department projects and

ongoing initiative of the division to make incremental improvements in cooperation with Public Works Department projectory other community projects.

Other Project Total 200,000

Equipment

200,000

		A	Adopted 202	1	F	Projected Re	equirements	S	
	Prior	Reappro-			2222		2224		Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund			40,000	40,000	40,000	40,000	40,000	40,000	200,000
Total			40,000	40,000	40,000	40,000	40,000	40,000	200,000

**Division:** Water Project Priority: 8

Project Title: Water Service Upgrade Program
Start Date: 01/21
End Date: 12/25

End Date:
Description:

The water service upgrade program was initiated in 1997, and has been an ongoing division initiative to allow a number of residents to upgrade their individual water services. The division proposes to continue offering this program in 2021. Numerous water services, from the main to the residence, are in need of replacement to KPU standards. After completion of the work and inspection by the division, this program allows the customer to provide cost documentation and receive a grant-in-aid. \$500 is available for work undertaken on private property and up to \$4,000 is available for work undertaken within the right-of-way. As a result of homeowners participating in the program, KPU will assume full responsibility for future repairs within the right-of-way as long as they are not caused by negligence on the part of the property owner.

Project Number:

Design

Land/Right-of-Way

Construction Management

Construction 75,000

Equipment Other

Project Total 75,000

		A	Adopted 202	1	F	Projected R	equirements	8	
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund			15,000	15,000	15,000	15,000	15,000	15,000	75,000
Total			15,000	15,000	15,000	15,000	15,000	15,000	75,000

Division: Water Project Priority: 9

Project Title:Backflow Prevention ProgramStart Date:01/21End Date:12/25

### **Description:**

This grant-in-aid program was established in 1995, and has been an ongoing division initiative to encourage businesses to install backflow preventers to help protect the municipal water system. The division proposes to continue offering this program in 2021 with an increased reimbursement amount. This program is part of ADEC's mandated cross-connection control regulations, which require the Utility to be responsible for system-wide protection. Until 2001, Ketchikan's lack of adoption and enforcement of the Uniform Plumbing Code allowed many substandard installations to be constructed within the City. Older sprinkler systems with just a single check are a particular problem. They cannot be tested and they leak contaminated water into the municipal system any time the water main is isolated and drained for repairs. Currently, at least 19 systems in need of backflow preventer installation and would benefit from this program to become compliant. The program as previously offered has not provided much incentive for businesses to make the upgrade, and the last time a business took advantage of the program was in 2017. In an effort to encourage business owners to become compliant to protect the City's water system, reimbursement to the property owner is now limited to 50% of the installed cost of the backflow preventer, or \$3.000, whichever is the lesser.

Project Number:

Design

Land/Right-of-Way

Construction Management

Construction 75,000

Equipment

Other

Project Total 75,000

		Δ.	Adopted 202	1	Projected Requirements				
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund			15,000	15,000	15,000	15,000	15,000	15,000	75,000
Total			15,000	15,000	15,000	15,000	15,000	15,000	75,000

**Division:** Water **Project Priority:** Project Number: 10 Project Title: Highlands Reservoir Property Acquisition **Estimated Project Cost:** Start Date: 01/24 End Date: 12/24 Design Land/Right-of-Way **Description:** 270,000 Construction Management Ketchikan is located in Earthquake Seismic Zone 3 (major damage). The Highlands Reservoir provides modest fire protection for the surrounding residential area including the State Jail, the Library, and other commercial buildings on Construction

Equipment

Project Total

270,000

Other

Ketchikan is located in Earthquake Seismic Zone 3 (major damage). The Highlands Reservoir provides modest fire protection for the surrounding residential area including the State Jail, the Library, and other commercial buildings on Copper Ridge Lane. Ketchikan's last remaining wood-stave reservoir built in 1982 will not survive a significant earthquake, nor can it be economically retrofitted with additional shear protection. If damaged, there are no remaining sources of wood-stave repair parts to be found anywhere. The individual wooden staves are only held together by friction, and when they collapse during a severe earthquake, they will suddenly release 300,000 gallons of water causing significant damage downstream. Although discussions began in 2015 to acquire the necessary property needed to construct a modern, larger reservoir, the sale was never completed at the proposed price of \$270,000. Once purchased, site investigations should begin in 2024 before beginning the construction of a large, modern 650,000 gallon reservoir. The design and construction funding will take at least another 8-10 years before the project is complete, and construction would begin around 2028 with an expected cost of about \$5 - 8 million.

			Adopted 2021			Projected R			
Source of Eundo	Prior	Reappro-	New						Total
Source of Funds	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Bonds - ADWF Loan							135,000		135,000
Proposed State 50% Municipal Assistance Fund	ling						135,000		135,000
Total							270,000		270,000

Department: Water Project Priority: 11

Project Title: Second Avenue Utility Improvements
Start Date: 01/22
End Date: 12/25

#### **Description:**

Second Avenue's cast-iron water mains were originally installed in a number of segments between 1956 and 1958. Only the failing water and sewer portion between Madison and Adams Streets was replaced in 2001. Since then, there has been no further progress replacing the remainder of this fragile, old 6-inch cast-iron water main and there have been four further failures in the 1275-foot portion between Adams and White Cliff. Long overdue for water and sewer replacement with non-corrodible plastic pipe. There is no present funding available for its replacement but if there were, it would be a joint venture between Public Works and the Water Division to be designed in 2022 with each of these four utility improvement projects contributing to the combined design contract with a single firm. Should Municipal Assistance Funding ever become available again, this would be a likely project that is already designed and has received ADEC approval for maximum points. It would also require voter approval to enter into loan agreements for the remainder of the funding. If granted, construction could begin in 2025.

Project Number:

Estimated Project Cost:

Design 15,000

Land/Right-of-Way

Construction Management

Construction 1,300,800

Equipment Other

Project Total 1,315,800

			<i> </i>	Adopted 202	1		Projected R	equirement	S	
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund Proposed 50% State Municipal Assistance Proposed Revenue Bonds - ADWF Loan	Funding					15,000			650,400 650,400	15,000 650,400 650,400
Total						15,000			1,300,800	1,315,800

Division: Water	Project Priority:	12	Project Number:

Project Title:West Fairy Chasm Utility ImprovementsStart Date:01/22End Date:12/25

#### Description:

This 8-inch ductile iron main was installed in 1981. The portion replaced in 2007 failed in a different manner than usually occurs. Unlike electrolytic corrosion that usually creates fairly small pits along the bottom of the pipe where the soils are moist and most conductive; in this case, the entire surface of the pipe was badly pitted. The soil layer around the pipe was black from dissolved iron and smelled slightly of sulfur. There is a possibility that the ductile iron pipe was bedded using rock that contains quite a bit of iron pyrite (fools gold) which is actually iron disulfide. Pyrites reacting with oxygen and water will form *Thiobacillus* bacteria which generate their energy through oxidizing the iron with a side effect of producing sulfuric acid, which chemically corrodes the iron pipe. Subsequent repairs made in 2017 at the Black Bear intersection have shown similar pitting and the ductile iron sewer mains are very likely in the same condition. The entire 720 foot section should be replaced with non-corrodible HDPE plastic pipe. There is no present funding available for its replacement but if there were, it would be a joint venture between Public Works and the Water Division to be designed in 2022 with each of these four utility improvement projects contributing to the combined design contract with a single firm. Should Municipal Assistance Funding ever become available again, this would be a likely project that is already designed and has received ADEC approval for maximum points. It would also require voter approval to enter into loan agreements for the remainder of the funding. If granted, construction could begin in 2025.

Estimated Project Cost: Design Land/Right-of-Way	15,000
Construction Management Construction Equipment	550,600
Other Project Total	565,600

		Adopted 2021				5	<u> </u>		
Source of Funds	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund Proposed 50% State Municipal Assistance Funding Proposed Revenue Bonds - ADWF Loan					15,000			275,300 275,300	15,000 275,300 275,300
Total					15,000			550,600	565,600

Department: Water	Project Priority:	13	Project Number:	
Project Title: Skyline Water Main Replacement	Start Date:	01/22	Estimated Project Cost:	
	End Date:	12/25	Design	10,000
Description:			Land/Right-of-Way	
The 560-foot ductile-iron 8-inch water line serving Skyline Condomin dedicated right-of-way but rather through a series of easements the Jackson, then across Skyline Condominium's property, and finally contitude it too is continuing to fail due to electrolytic corrosion and is overdupipe. There is no present funding available for its replacement but if	Construction Management Construction Equipment Other	360,800		
each of these four utility improvement projects contributing to the Municipal Assistance Funding ever become available again, this whas received ADEC approval for maximum points. It would also received the remainder of the funding. If granted, construction could begin in	Project Total	370,800		

			4	Adopted 202	21		Projected R	equirements	S	
Course of Funds	Fund	Prior	Reappro-	New	Total	2022	2022	2024	2025	Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund Proposed 50% State Municipal Assistance Proposed Revenue Bonds - ADWF Loan	e Funding					10,000			180,400 180,400	10,000 180,400 180,400
Total						10,000			360,800	370,800

Department: Water	Project Priority:	14
-------------------	-------------------	----

Project Title:Denali Avenue Utility ImprovementsStart Date:01/22End Date:12/25

#### **Description:**

Denali Avenue's cast-iron 6-inch water mains between Hill & Tower Roads were installed in two segments beginning in 1968 and completed in 1969. Like other cast-iron mains, it is fragile. In just this one block segment, there have already been three failures. The 635-foot segment is overdue for both water and sewer replacement with non-corrodible plastic pipe. There is no present funding available for its replacement but if there were, it would be a joint venture between Public Works and the Water Division to be designed in 2022 with each of these four utility improvement projects contributing to the combined design contract with a single firm. Should Municipal Assistance Funding ever become available again, this would be a likely project that is already designed and has received ADEC approval for maximum points. It would also require voter approval to enter into loan agreements for the remainder of the funding. If granted, construction could begin in 2025.

Project Number:	
Estimated Project Cost:	
Design	15,000
Land/Right-of-Way	
Construction Management	
Construction	512,000
Equipment	

527,000

Other

Project Total

		Adopted 2021								
Source of Funds	Fund No.	Prior Years	Reappro- priated	New Funding	Total	2022	2023	2024	2025	Total Project
Revenue Generating Fund Proposed 50% State Municipal Assistance Proposed Revenue Bonds - ADWF Loan	Funding					15,000			256,000 256,000	15,000 256,000 256,000
Total						15,000			512,000	527,000

Department: Water	Project Priority:	15	Project Number:	
Project Title: Evergreen Ave. Utility Improvements	Start Date:	01/22	Estimated Project Cost:	
	End Date:	12/25	Design	15,000
Description:			Land/Right-of-Way	

Construction Management

440,000

Construction

Evergreen Avenue's 548-feet of water main between Hill and Tower Roads was installed in two segments; the first 281-feet of 6-inch cast-iron was installed in 1970 followed by the final 267-feet in ductile-iron in 1976. The cast-iron portion has been particularly troublesome with several failures. The entire 548-foot segment is overdue for both water and sewer

has been particularly troublesome with several failures. The entire 548-foot segment is overdue for both water and sewer replacement with non-corrodible plastic pipe. There is no present funding available for its replacement but if there were, it would be a joint venture between Public Works and the Water Division to be designed in 2022 with each of these four utility improvement projects contributing to the combined design contract with a single firm. Should Municipal Assistance Funding ever become available again, this would be a likely project that is already designed and has received ADEC approval for maximum points. It would also require voter approval to enter into loan agreements for the remainder of the funding. If granted, construction could begin in 2025.										
			Δ.	Adopted 202	1	Projected Requirements				
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						15,000				15,000

Department: Water Project Priority: 16

**Project Title:** Utility Vehicles **Start Date:** 01/22

End Date: 12/25

#### **Description:**

Replacement in 2022 of Vehicle 46, a Chevrolet Blazer purchased in 2000. This vehicle has all the mechanical, rust, maintenance issues that can be expected for a vehicle of its age in Ketchikan. The replacement vehicle is planned to be a Ford Explorer with all wheel drive capability and can be purchased in 2022 utilizing the State of Alaska's contract purchasing. Vehicle 66, the single axle dump truck jointly shared by the Electric and Water Divisions was purchased in 2003. Already 18 years old, it is reaching the end of its useful service life with mechanical issues. It is proposed for replacement in 2023 for \$118,000. Similarly, the oldest of the two small Kubota rubber tracked backhoes that are also jointly shared by the divisions was purchased in 2007. Supremely useful in tight situations where a large, rubber-tired backhoe won't fit, it too is reaching the end of its useful service life. A replacement small backhoe from a local vendor is estimated to cost \$85,000 today. With an allowance of 2.5% inflation until 2024, this would be equivalent to \$94,000.

# Project Number:

**Estimated Project Cost:** 

Design

Land/Right-of-Way

**Construction Management** 

Construction

Equipment 249,500

Other

Project Total 249,500

			Adopted 2021			Projected Requirements				
	Fund	Prior	Reappro-	New						Total
Source of Funds	No.	Years	priated	Funding	Total	2022	2023	2024	2025	Project
Revenue Generating Fund						37,500	118,000	94,000		249,500
Total						37,500	118,000	94,000		249,500